



Canadian  
Construction  
Association

# COVID-19 - Standardized Protocols for All Canadian Construction Sites

Version 2

March 30, 2020

For inquiries: Contact Zack Mullins  
at [zmullins@cca-acc.com](mailto:zmullins@cca-acc.com)

## TABLE OF CONTENTS

<u><a href="#">Standardized Protocols for All Canadian Construction Sites</a></u>	<u><a href="#">1</a></u>
<u><a href="#">Prevention measures</a></u>	<u><a href="#">1</a></u>
<u><a href="#">Communication and awareness</a></u>	<u><a href="#">1</a></u>
<u><a href="#">Business-related travel</a></u>	<u><a href="#">2</a></u>
<u><a href="#">Working remotely</a></u>	<u><a href="#">2</a></u>
<u><a href="#">Access and movement to/from construction site</a></u>	<u><a href="#">2</a></u>
<u><a href="#">Construction site and site trailer cleaning protocols</a></u>	<u><a href="#">2</a></u>
<u><a href="#">Limiting and removing internal touch point areas</a></u>	<u><a href="#">2</a></u>
<u><a href="#">Compartmentalization</a></u>	<u><a href="#">3</a></u>
<u><a href="#">Site operation</a></u>	<u><a href="#">3</a></u>
<u><a href="#">Deliveries</a></u>	<u><a href="#">3</a></u>
<u><a href="#">Other</a></u>	<u><a href="#">3</a></u>
<u><a href="#">Detection measures</a></u>	<u><a href="#">4</a></u>
<u><a href="#">Screening at entry of construction site</a></u>	<u><a href="#">4</a></u>
<u><a href="#">Response measures</a></u>	<u><a href="#">4</a></u>
<u><a href="#">Possible cases of COVID-19</a></u>	<u><a href="#">4</a></u>
<u><a href="#">Response plans</a></u>	<u><a href="#">4</a></u>
<u><a href="#">Other</a></u>	<u><a href="#">4</a></u>

---

## COVID-19 - STANDARDIZED PROTOCOLS FOR ALL CANADIAN CONSTRUCTION SITES

The Standardized Protocols for All Canadian Construction Sites outlines the best practices for construction sites in order to maintain the health and safety of all workers required to perform duties during the COVID-19 crisis. Some provinces and municipalities have implemented stricter measures than those found in this document, and contractors are responsible for compliance with the rules, regulations and practices required by the applicable authorities. The protocols, which include prevention, detection and response measures, will minimize the impacts of the crisis and ensure business continuity in the construction industry

The objectives of the Standardized Protocols are to:

- Prioritize the health and safety of workers and of their surrounding communities;
- Apply recommendations and best practices from federal, provincial and municipal Public Health Authorities to construction site procedures;
- Establish and maintain a common COVID-19 Pandemic Response Plan across construction sites; and
- Foster open communication amongst stakeholders and ensure a respectful work environment.

### Standardized Protocols for All Canadian Construction Sites

---

#### Prevention measures

---

##### *Communication and awareness*

- Clear signage is posted at entry points on the construction site and outline the commitment of the contractor to maintain health and safety measures during the COVID-19 crisis, with relevant updates from appropriate jurisdictions' public health authorities and self-identification screening tools.
- All workers exercise the following recommended practices for reducing the risk of transmission as identified by the Public Health Agency of Canada (PHAC), Health Canada, and Centers for Disease Control and Prevention:
  - o Avoid touching eyes, nose and mouth with unwashed hands;
  - o When coughing or sneezing:
    - Cough or sneeze into a tissue or the bend of your arm, not your hand;
    - Dispose of any tissues you have used as soon as possible in a lined waste basket and wash your hands afterwards;
  - o Clean and disinfect frequently touched objects and surfaces, including all reusable PPE;
  - o Do not share personal items or supplies such as phones, pens, notebooks, PPE, etc.;
  - o Avoid common physical greetings, such as handshakes;
  - o Maintain a minimum physical distance of two metres from others; and
  - o Wash hands often with soap and water for at least 20 seconds after using the washroom, when preparing food, and after blowing nose, coughing, or sneezing. If hands are not visibly soiled, and soap and water are unavailable, alcohol-based hand sanitizer can be used.



***Business-related travel***

- Non-essential business travel is not authorized. Business travel is limited and on an exceptional basis only.
- All individuals returning from out of country must undergo a 14-day self-isolation period, as mandated by the federal government and outlined here: [www.canada.ca/en/public-health/services/diseases/2019-novel-coronavirus-infection/latest-travel-health-advice.html](http://www.canada.ca/en/public-health/services/diseases/2019-novel-coronavirus-infection/latest-travel-health-advice.html).
- As some provincial governments impose similar restrictions for inter-provincial travel, any such requirements for self-isolation must be obeyed as applicable.

***Working remotely***

- Where practical, all office employees supporting a project work remotely. Meetings are held through teleconferencing or videoconferencing.

***Access and movement to/from construction site***

- Detailed tracking of worker's status on-site and off-site are kept at all time (e.g., fit to work, sick, off-work for family caring duties, etc.). A list of all quarantined workers is updated daily, with their privacy maintained.
- Wherever possible, workers travel to site using individual modes of transportation (e.g., personal vehicle or bicycle). Additional parking arrangements are made as required.
- All non-essential individuals are not permitted access to the site.

***Construction site and site trailer cleaning protocols***

- All offices and jobsites implement additional cleaning measures of common areas. All door handles, railings, ladders, switches, controls, eating surfaces, shared tools and equipment, taps, toilets, and personal workstation areas are wiped down at least twice a day with a disinfectant, such as disinfectant wipes. Individuals are responsible for cleaning and disinfecting their workstations.
- Additional sanitary measures are implemented on site: hand washing stations with a posted hand washing protocol, hand sanitizer stations, provision of disinfectant wiping products. These types of facilities are made available at site entries, exits, washrooms, eating areas, offices, and any other areas with commonly touched surfaces.
- Commonly touched surfaces on vehicles and equipment are thoroughly cleaned and disinfected at the end of shifts and between users.
- All cleaning and disinfecting is carried out as PHAC's recommends here: [www.canada.ca/en/public-health/services/publications/diseases-conditions/cleaning-disinfecting-public-spaces.html](http://www.canada.ca/en/public-health/services/publications/diseases-conditions/cleaning-disinfecting-public-spaces.html).

***Limiting and removing internal touch point areas***

- Limit access and use of shared devices like coffee machines, water fountains, microwave ovens, and similar. Means to clean and disinfect such devices between uses is provided.
- Limit use of common pens for sign-in sheet to construction site.
- Washroom modifications - Install more sinks and sinks with physical separation between users where feasible. Change out taps, paper towel dispensers and garbage cans to hands-free models.
- Remove doors/door handles - Look at all reasonable opportunities to remove them.



- Where touch points like door handles and water coolers remain, paper towels are provided to allow users to avoid skin contact.
- Gloves are worn whenever possible while on the worksite, but are treated the same as bare hands in terms of minimizing unnecessary touching of anything on site and the user's face.

### **Compartmentalization**

- The construction site is to be segregated to the extent possible in zones or other methods to keep different crews/trades physically separated at all time. This promotes physical distancing and supports the containment of propagation should it arise.
- Eating is restricted to clearly identified dedicated eating areas with handwashing stations, cleaning and disinfectant materials, and adequate space to maintain minimum physical distancing.
- Upper limits are put on the number of people allowed in each zone and in facilities like washrooms, trailers, and eating areas at once to allow for the recommended minimum physical distancing.
- One-way staircases are established wherever practical to minimize worker contact.
- Freight elevators are operated/occupied by only one individual at a time or where feasible, by respecting the minimum physical distancing guidelines.

### **Site operation**

- The number of in person meetings is minimized. If required, meetings should involve only necessary individuals and include six people or fewer. Minimum physical distancing is maintained, and meetings are held in open spaces when possible.
- The worksite is rearranged to reduce high-traffic areas and allow for the minimum physical distancing.
- Site teams are encouraged to put forward split/alternating shifts to avoid extensive intermingling. Voluntary shift offset and implementing time gaps between shifts are highly encouraged.
- Alternate arrangements are made as necessary to ensure workers avoid breaking the minimum physical distance with others for prolonged periods. When this is not feasible, plans are made to minimize the duration of the task. For any work that ultimately must be done in close-proximity, workers are to wear additional PPE as appropriate for the specific task in order to minimize the risk.
- Project teams stagger break and lunch schedules to minimize the number of people in close proximity to one another. Enclosed lunchrooms are only made available during inclement weather.
- Work schedules are adjusted to provide time for proper cleaning and disinfecting as required.

### **Deliveries**

- Delivery zones are clearly identified and limited to receivers and deliverers only.
- When possible, nothing is passed between the deliverer and the receiver (e.g. shipment documents and pens for signatures). Deliveries are unloaded solely by receivers using proper PPE, while deliverers remain in their vehicles.

### **Other**

- Any other measures deemed to increase the safety or limit the propagation of the virus.



---

## Detection measures

---

### *Screening at entry of construction site*

- Before entering the site, individuals must confirm that:
    - They are not currently exhibiting flu-like symptoms such as fever, tiredness, coughing, or congestion;
    - They have not returned from outside of Canada within the past 14 days; and
    - They have not been in contact with someone with a confirmed or probable case of COVID-19.
  - Workers who are not authorized to access the site are to be safely transported directly back home, or to a preferred location of self-isolation. When unable to do so themselves, a vehicle and driver will be arranged for them. Both driver and passenger are to be given masks and nitrile gloves. The passenger is to sit in the backseat, and the driver is to open and close the doors for them.
- 

## Response measures

---

### *Possible cases of COVID-19*

- Individuals who have been potentially exposed to the virus, or who are exhibiting flu-like symptoms such as fever, tiredness, coughing, or congestion are instructed to:
  - Not come to work;
  - Contact their supervisor and/or human resources department;
  - Stay at home and self-isolate; and
  - Contact local health authorities for further direction.Such individuals are required to follow the recommendations of the local health authority and may not return to work until given approval by the proper health authorities.
- Individuals who begin to display flu-like symptoms on site are instructed to avoid touching anything, take extra care to contain coughs and sneezes, and return home immediately to undergo a 14-day self isolation period.
- All areas on site potentially infected by a confirmed or probable case are barricaded to keep individuals two metres away until the area is properly cleaned and disinfected.

### *Response plans*

- All contractors are to complete an integrated continuity plan to respond to partial or complete shutdown of construction sites or in the case of a severe limitation of site operations.

### *Other*

- Refer to [www.canada.ca/en/public-health/services/diseases/coronavirus-disease-covid-19.html](http://www.canada.ca/en/public-health/services/diseases/coronavirus-disease-covid-19.html) for the latest information.
- 

The situation related to COVID-19 is changing rapidly. This Protocol will be updated on an as required basis to reflect the latest broadly adopted measures.

---

